

BILL ITEMS

Schedule: SAMPLE PROJECT
 Bill: SINGLE PLY MEMBRANE

ID	Description	Unit	Quantity	Rate	Total £
A	<u>FATRAFOL FF810 MECHANICALLY FIXED MEMBRANE</u>				
	Labour and materials in single ply roofing system comprising; polythene vapour control layer with all laps sealed and taped, PIR foil faced uniform insulation board and Fatra 1.5mm thick FF810 mechanically fixed membrane; all fixed in accordance with manufacturers instructions to profiled metal deck (measured elsewhere)				
A	0.18 U value; Uniform PIR Insulation; 20 year product guarantee; flat board - steelwork laid to falls	m2	2,325		
B	ditto; tapered	m2	2,804		
C	<u>Steel Decking</u>				
	Labour and materials in steel decking; fixed in accordance with manufacturers instructions to cold rolled purlins to falls				
C	32/1000 0.75mm thick steel decking	m2	5,129		
D	<u>Abutments / Trims / Accessories</u>				
	forming upstand to parapet; 200mm high; uninsulated; including galvanised steel to form upstand fixed to others SFS frame; dressing membrane and vcl over parapet	m	418		
E	weathering membrane to rooflight	m	308		
F	ditto; abutment to external wall; 200m high upstand	m	114		
G	ditto; to covered walkway rooflight	m	46		
H	ditto; 450mm high	m	17		
I	ditto; max 1300mm high; insulated and including metal decking backing fixed to others support steelwork	m	100		
J	ditto; 860mm high; insulated and including metal decking backing fixed to others support steelwork	m	59		
K	weathering fatra laminated drip metal to perimeter of pop up roofs; dressing over fascia (measured elsewhere)	m	207		
L	ditto; max 1300mm high; insulated and including metal decking backing fixed to others support steelwork; to lift over run	m	6		
M	extra over; forming sumped gutter	m	442		
c/f					

BILL ITEMS

Schedule: SAMPLE PROJECT

Bill: SINGLE PLY MEMBRANE

ID	Description	Unit	Quantity	Rate	Total £
b/f A	compsite membrane lined gutter to atrium glazing gridline 12	m	22		
B	extra; stop ends	nr	2		
	Outlets				
C	100mm Domed Outlet	nr	42		
D	weir overflows	nr	8		
	Penetrations				
E	weathering to SVP; 100mm	nr	11		
	Paving Slabs				
F	600 x 600 x 50mm	m2	377		
	Standing Seam				
G	extra over roof area; Fatra standing seam profile to stair core roof	m	56		
	<u>WALL CLADDING TO OPEN TEACHING SPACE</u>				
H	Labour and materials in composite micro ribbed complete with preformed corners, top hats vertical joint and cill flashing	m2	47		
	To Summary £				

BILL ITEMS

Schedule: SAMPLE PROJECT

Bill: PRELIMS

ID	Description	Unit	Quantity	Rate	Total £
	<u>Drawing</u>				
	A Provision of working drawings	item	1		
	<u>Off-loading & Distribution</u>				
	B Crane visits for loading metal deck	visit	4		
	C Crane visits for loading insulation & membrane	visit	4		
D	Labour in horizontal distribution of materials	item	1		
	<u>Safety Netting</u>				
	E Erection and dismantling of safety netting using MEWPS to facilitate the safe installation of metal decking	item	1		
	To Summary £				

SUMMARY

Schedule: SAMPLE PROJECT

Bill Name	Total £
SINGLE PLY MEMBRANE PRELIMS	
Total £	